BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2020-21/OW/WORK_INDENT42419

APPROVED SCHEDULE - B

EE/BTP/BBMP/E-PMT/02/2020-21, Date: 28.05.2020

me of Work:Office Maintenance and Crematorium Maintenance in Ward No.8

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of SRIKANTH K S (AAKAR CONSTRUCTION)	
				In Figures	In Words
1	383.92	KSRB 15-16.1 : Providing and finishing external walls in two coats with waterproof cement paint of approved brand and shade to give an even shade after throughly brooming the surface to remove all dirt and loose powdered material, free from mortar drops and other foreign matter cost of materials, labour, complete as per specifications. - with primer. (P. No. 120, I.No. 15.53.2 of SR 2018-19).	Sqm	100.58	Rupees One Hundred and Fifty Eight Paise Only
2	460.9	KSRB 15-15.1 : Providing and applying painting in two coats with plastic emulsion paint of approved brand on wall surface to give an even approved shade after thoroughly brushing the surface, free from mortar drops and other foreign matter including preparing the surface even and sand paper smooth, cost of materials, labour, complete as per specifications. - with primer. (P. No: 116, I.No. 15.51.2 of SR 2018-19). with Primer	Sqm	88.74	Rupees Eighty Eight and Seventy Four Paise Only
3	0.45	KSRB 7.7 : Providing and fixing in position in cement concrete 1:3:6 steel glazed windows and ventilators side hung/top hung fully openable as per approved drawings using Z angles of 25x33x3mm, weighing 1.419 Kg/m both for outer and inner frames and central mullion section of size 25x46x3mm. weighing 2.28Kg/m duly providing T section 19x19x3mm weighing 0.839 kg/m for glazing of windows not more than 34 cms. c to c including providing and fixing 4mm. thick reeded glass with teakwood beading of required size, all steel sections should confirm to I.S 7452:1990, 4nos. of holdfasts of approved size, section should be cut to length welded and electrically grinded subdividing frames of unit shall be tenonned and revetted into the frames electrically. All the steel surface shall be throughly cleaned free of rust and painted with one coat of anti-corosive paint and finishing with two coats of ready mix paint of approved colour and make including cost of materials, fixtures, labour and HOM of machinerycomplete as per specifications. Specification No. KBS 7.12.1 / 7.12.2 / 7.12.3 / 7.12 (Page No : 34, item No :7.7)	Sqm	3843.58	Rupees Three Thousand Eight Hundred Forty Three and Fifty Eight Paise Only
4	0.12	KSRB 9.4-3 : Providing Mathi / Nandi wood frames of doors, windows, clerestory windows, ventilators and other frames, wrought, framed or assembled including making plaster groves (excluding cost of cement concrete and side clamps), but including cost of materials, labour, HOM of machineries complete as per specifications. Specification No. KBS 9.33 (Page No : 53, item No :9.12 SR 2018-19)	Cum	72174.18	Rupees Seventy Two Thousand One Hundred Seventy Four and Eighteen Paise Only
5	3.46	KSRB 9-7.3 :Providing and fixing in position fully panelled Mathi/ Nandi wood shutters for doors, styles and rails of 30mm. thick with bottom and lock rails 180mm wide top rail and styles 100mm wide as per drawing and panels of 25mm thick including cost of materials, labour, HOM of machineries complete as per specifications. (excluding cost of fixtures) Specification No. KBS 9.34 (Page No : 53, item No :9.22 SR 2018-19)	Sqm	3763.71	Rupees Three Thousand Seven Hundred Sixty Three and Seventy One Paise Only
6	29.48	KSRB 15-17.4 : Applying priming coat over new wood surface and / or wood based surface, after brushing with ready mix enamel priming paint including preparing the surface after thoroughly cleaning oil, grease, dirt and foreign matter, sand papering and knotting ready mix paint including cost of materials, labour, complete as per specifications.(Page. No. 121 Item No. 15.58 SR 2018-19)	Sqm	49.3	Rupees Forty Nine and Thirty Paise Only
7	29.48	Providing and applying painting two coats (excluding priming coat) on new wood surface and / or wood based surface with enamel paint to give an even shade, cleaning the surface of all dirt, dust and foreign matter, sand papering including cost of materials, labour, complete as per specifications.(Page. No. 121 Item No. 15.60.1 SR 2018-19)	Sqm	95.65	Rupees Ninety Five and Sixty Five Paise Only

Signature of the contractor

27/07

Executive Engineer

Sl. No.	Approved Qty.	Description	Unit	Approved Te... SRIKANTH K S... CONSTRUCTI...	
				In Figures	In Wo...
8	1	KSRB 13-11.1 : Providing and placing on terrace, polyethylene water storage tanks as per IS 12701 : 1996 with manhole lid and suitable locl<ing arrangements, making holes of suitable diameter for inlet, outlet and over flow pipes, including cost of all materials, labour, transport charges, HOM of equipments and testing complete as per specifications.(For 1000 litre capacity) Specification No.KBS 13.22 (P.No.96, I.No.13.78 of PW, P&IWTD S.R 2018-19)	each	6732.68	Rupees Six Thousand Seven Hundred Thirty Two and Sixty Eight Paise Only
9	40	Providing and fixing Chorinated Poly Venyl Chloride (CPVC) pipes conforming to IS 15778, having thermal stability for hot and cold water supply including all CPVC plain and brass threaded fittings including fixing the pipe with clamp at 1.00 mtr spacing. This includes jointing of pipes and fittings with one step CPVC solvent cement & the cost of cutting chases & making good the same including testing of joints complete. (Concealed work including cutting chases and good the walls etc.) - 20mm nominal OD pipes. (P.No.99, I.No. 13.86.2 of KPWD SR 2018-19)	m	231.72	Rupees Two Hundred Thirty One and Seventy Two Paise Only
10	40	Providing and fixing Chorinated Poly Venyl Chloride (CPVC) pipes conforming to IS 15778, having thermal stability for hot and cold water supply including all CPVC plain and brass threaded fittings including fixing the pipe with clamp at 1.00 mtr spacing. This includes jointing of pipes and fittings with one step CPVC solvent cement & the cost of cutting chases & making good the same including testing of joints complete. (Concealed work including cutting chases and good the walls etc.) - 25mm nominal OD pipes(P.No.99, I.No. 13.86.3 of KPWD SR 2018-19)	m	288.91	Rupees Two Hundred Eighty Eight and Ninety One Paise Only
11	3	KSRB 11-15.3 : Providing and fixing 453x357mm dia rectangular shape mirror with plastic moulded frame of approved make and shade with 6mm thick hard board backing including cost of materials, labour complete as per specifications. (P.No.84, I.No. 12.41 of KPWD SR 2018-19)	unit	1120.14	Rupees One Thousand One Hundred Twenty and Fourteen Paise Only
12	2	Providing and fixing 7.5 cms to 15.00 cms dia NP grating 100 mm dia. (P.No. 90, I.No. 12.111 of KPWD SR 2018-19)	each	147.91	Rupees One Hundred Forty Seven and Ninety One Paise Only
13	3	Providing and fixing CI Nahani trap of approved make conforming to ISI specifications and construction of Cistern in M-15 as per directions (Rate is inclusive of cost of materials and fixtures and conveyance of materials to work spot). - 10cms x 7.5cms (P.No. 90, I.No. 12.113.1 of KPWD SR 2018-19)	each	246.51	Rupees Two Hundred Forty Six and Fifty One Paise Only
14	5	KSRB13-6.1-1 : Providing and fixing in position brass bib cock of approved quality 15mm nominal bore including cost of all materials, labour and HOM of equipments with all leads complete as per specifications. Specification No.KBS 13.2.2 / 13.3 (P.No. 93, I.No. 13.23 of KPWD SR 2018-19)	each	187.35	Rupees One Hundred Eighty Seven and Thirty Five Paise Only
15	3	KSRB13-6.3-3 : Providing and fixing in position brass gate valve with C.I wheel of approved quality (screwed end) 25mm nominal bore including cost of all materials, labour and HOM of equipments with all leads complete as per specifications. Specification No.KBS 13.2.6 / 13.3. (P.No.94/ I.No. 13.34 of KPWD SR 2018-19)	each	442.73	Rupees Four Hundred Forty Two and Seventy Three Paise Only
16	2	KSRB13-6.3-3 : Providing and fixing in position brass gate valve with C.I wheel of approved quality (screwed end) 20mm nominal bore including cost of all materials, labour and HOM of equipments with all leads complete as per specifications. Specification No.KBS 13.2.6 / 13.3. (P.No.93/ I.No. 13.33 of KPWD SR 2018-19)	each	331.31	Rupees Three Hundred Thirty One and Thirty One Paise Only
17	2	KSRB 11 -6 : Providing and fixing white vitreous china clay, water closet European type (Pedestal type, S-trap) with black solid plastic seat and lid, C.P brass hinges, rubber buffers. 10 litre white glazed I vitreous china clay low level, flushing cistern (all are approved make) with fittings, C.1 I M.S brackets, 40mm diameter flush bend with fittings and clamps, overflow arrangements with specials and 25mm mosquito proof coupling of approved design, painting of fittings and brackets, cutting and making good the wall and floor wherever required, including cost of materials, labour complete as per specifications.(P.No.79 I.No.12.5 of KPWD SR 2018-19)	Each	4886.81	Rupees Four Thousand Eight Hundred Eighty Six and Eighty One Paise Only

Signature of the contractor

Executive Engineer

	Approved Qty.	Description	Unit	Approved Tender Rates of SRIKANTH K S (AAKAR CONSTRUCTION)	
				In Figures	In Words
18	2	KSRB 11-11.1 : Providing and fixing white vitreous china clay, flat back wash basin size 630x450mm with a pair of 15mm C.P brass pillar taps with C.I / M.S brackets, 32 mm C.P. brass waste of standard pattern, painting of fittings and brackets, cutting and making good the wall and floor wherever required, including cost of materials, labour complete as per specifications. Specification No. KBS 11 (P.No.82 I.No.12.23 of PWDSR 2018-19)	unit	3951.06	Rupees Three Thousand Nine Hundred Fifty One and Six Paise Only
19	2	KSRB 11-7.1 : Providing and fixing white vitreous china clay, flat back, lipped front urinal basin of 430x260x350mm with 5 litres PVC automatic flushing cistern, C.I / M.S brackets, standard flush pipe and C.P. brass spreaders with brass unions and G.I. clamps complete painting of fittings and brackets, cutting and making good the wall and floor wherever required, including cost of materials, labour complete as per specifications. Specification No. KBS 11 (P.No.80 I.No.12.7 of PWDSR 2018-19)	unit	3029.11	Rupees Three Thousand Twenty Nine and Eleven Paise Only
20	157.49	KSRRB M800-7. Painting:-Providing and applying two coats of ready-mix paint of approved brand after through cleaning of surface to give an even shade complete as per specifications.MORTH Specification No. 803 Painting on Steel Surface(P.No.181, I.No24.8.1 of PW,P&IWTD S.R 2018-19))	Sqm	70.99	Rupees Seventy and Ninety Nine Paise Only
21	5.04	Providing and fixing M.S. Hand railing for Balcony with 50mm dia. M.S. hollow pipe of 14 gauge, welded to 20mmx20mm M.S. square rod placed vertically, spaced at 100mm at regular intervals of 600mm. These vertical rods laterally tied to 3 horizontal rods spaced at equal interval. These assembly is fixed to concrete by using expansion bolts and welding the same to reinforcement bars and making good the surface. All the joints and sections hould be cut to length, welded and grinded wherever necessary etc., complete . The work includes cost of all materials, labour charges for all items of work, hire charges for welding, cutting and grinding equipment, and electricity charges, etc., complete as per specification and drawing.Specification No. KBS 11 (P.No.40 I.No.7.35 of PWDSR 2018-19)	Sqm	2800.35	Rupees Two Thousand Eight Hundred and Thirty Five Paise Only
22	1.5	KSRRB M300-1. Earth work excavation by manual means in ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5m, excavated surface levelled and sides neately dressed, the disposed earth to be levelled neatly after breaking of clods complete as per specification. MORTH / Chapter 3 (P.No.143, I.No.19.1 of PW, P&IWTD SR 2018-19)	Cum	230.52	Rupees Two Hundred Thirty and Fifty Two Paise Only
23	1	KSRRB M400-19: Construction of Median and island above road level with approved material deposited from borrowpits, spread, sloped and compacted as per Clause 400.7 complete as per specifications. MORTH Specification No.407 (P.No155 of I.No.20.20 in PW,P&IWTD SR 2018-19)	cum	202.27	Rupees Two Hundred Two and Twenty Seven Paise Only
24	10	KSRB 14.6-1: Providing & laying heavy duty cobble stones 60mm thick interlock pavers,using cement & course sand for manufacture of blocks of approved size ,shape and colour with a minimum compressive strength of 281 kg per sqm over 50mm thick sand bed (Avg thickness) and compacting with plate vibrator having 3 tons compaction force thereby forcing part of sand underneath to come up in between joints, final compaction of paver surface joints into its final level, including cost of materials, labour and HOM of machineries complete as per specifications. Specification No. KBS (P.No 103 of I.No.14.6 in PW,P&IWTD SR 2018-19)	Sqm	1019.07	Rupees One Thousand Nineteen and Seven Paise Only

Signature of the Contractor

Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92